

Reconstruction of the Lincoln Avenue Bridge over the NEC Rail Line, an Inactive Rail Yard, and the Assunpink Creek City of Trenton, Mercer County

Public Information Center #1

December 7 – 18, 2020

GPI Engineering | Design | Planning | Construction Management



Presentation Overview

- Project Team
- Project Delivery Process
- Project Location / Limits
- Purpose and Need
- Existing Conditions
- Approved Project Plan
- Construction Staging
- Detour
- Project Schedule and Construction Cost Estimate
- Feedback



Project Team



Aaron T. Watson – Deputy Administrator/Director DOT&I
George A. Fallat, PE – County Engineer
Basit A. Muzaffar, PE (Sunny) – Project Manager, Assistant
County Engineer



Kyle Skala – Bureau of Local Aid and Economic Development



John Coscia, Jr. – Manager, Office of Project Implementation




Bernard Boerchers, PE, PTOE – Project Manager William Farrow, PE – Deputy Project Manager



Project Delivery Process


Local Concept Development	Local Preliminary Engineering	Final Design / Right of Way Acquisition	Construction
Purpose and Need Statement	Approved Design Exception Report	Construction Contract	Completed Construction
Data Collection and Environmental Screening Report	Cost Estimates (Final Design ROW and Construction)	Document and PS&E Package Environmental Reevaluations	As-Builts Update and Finalize Design
Selection of Preliminary Preferred Alternative	Approved Environmental Document	Environmental Permits	Communications Report
NEPA Classification	Approved Project Plan	Acquisition of ROW Update Design	Close-Out Documentation
Concept Development Report	Preliminary Engineering Report	Communications Report	
Create Design Communications Report	Update Design Communications Report		





Purpose and Need

- Purpose is to replace Structure No. 1100-055 (County No. 140.9)
- Rated **3-Serious** due to condition of the superstructure
 - Deck rating: 4-Poor
 - Superstructure rating: 3-Serious
 - Substructure rating: 5-Fair
- Sufficiency Rating of 46.2







Existing Conditions (Bridge)

Structural Information and Deficiencies

- Carries Lincoln Avenue over Amtrak NEC and Assunpink Creek
- Built in 1931
- Reconstructed in 1965
- Comprised of 8 simple spans
- Steel through-girders (fracture critical)
- Steel floorbeams and concrete deck
- Severely corroded steel
- Large areas spalled / delaminated concrete
- Substandard vertical underclearance





Existing Conditions (Roadway)



Roadway Information and Deficiencies

- 2 lane, urban minor arterial
- Not posted (25 mph)
- 18-foot wide lanes, no shoulders (CSDE)
- 6-foot wide sidewalk on either side
- Roadway/pedestrian lighting
- Broken back horizontal curves
- Substandard vertical stopping sight distance
- Substandard cross slope
- Clear zone (14-16') with obstructions



Existing Conditions (Rail)

Railroad Operations

- Amtrak Northeast Corridor (NEC)
 - Amtrak
 - NJ Transit
 - Freight
- 5 mainline and 1 siding electrified tracks
- Overhead catenary lines and feeder cables
- Inactive NJ Transit tracks and old platform







Existing Conditions (Environmental Constraints)

USGS STREAM GAUGE STATION

LINCOLN AVE

NORTHEAST CORRIDOR

HAMPTON AVE

CHAMBERS ST

MONMOUTH ST


ASSUNPINK CREEK (FW2-NT) 50' RIPARIAN ZONE

LEGEND


NJDEP Known Contaminated Site List

SCIENT ESE HI SE SE

- Special Concern Habitat (Great Blue Heron Foraging)
- Brownfield Development Area (NJDEP 2013) Stream (NJDEP SWQS FW2-NT) Wetlands 2007 (NJDEP LU/LC)
- vvenanus 2007 (NJDEP LU/LC
- <u>e.</u>...
- FEMA/NJDEP Flood Hazard Area
- Riparian Zone (50 Ft)
- 🚽 Floodway Limit
- Pennsylvania Railroad New York to Philadelphia Historic District
- Historic Fill Location
- Historic Property (Eligible Status)




Approved Project Plan






Construction Staging



STAGE 1 - CONSTRUCTION



Construction Staging



STAGE 2 - CONSTRUCTION



Approved Project Plan (Detour)

Lincoln Ave

N Clinton Ave

Assumplink Creel



1

E State St

Olden Ave

Detour EB Traffic

Maintain WB Traffic One-Way

Project Schedule and Construction Cost Estimate



Estimated Construction Cost: \$38 Million Dollars (in 2020 dollars) Estimated Right of Way Costs is \$1 Million Dollars



Public Feedback

Submit Questions, Comments and Suggestions at the link below:

> For more information contact: George Fallat, P.E., County Engineer DOT&I Mercer County, Division of Engineering 640 South Broad Street Trenton, NJ 08650-0068 Email: gfallat@mercercounty.org